

# TOWN OF FULTON

2738 W. Fulton Center Dr.  
Edgerton, Wisconsin 53534

Connie Zimmerman, WCMC, CMTW  
Clerk/Treasurer

Phone: 608-868-4103  
Fax : 608-868-4104  
Email: [fultonclerk@townoffulton.com](mailto:fultonclerk@townoffulton.com)  
Web site: [www.townoffulton.com](http://www.townoffulton.com)

August 7, 2015

## COURTESY NOTICE

### 2015 Seal Coat (Slag/Stone Aggregate) Projects

Dear Town of Fulton Resident:

**FAHRNER ASPHALT SEALERS** will be sealing

- Woodlands subdivision – E. Wildwood Way, N. Woodsvie Crossing, E. Prairieview Dr., N Heritage Ridge, Lakeside Dr. & Ct.
- N. Gladys Dr. East & West, E. Mallwood Dr. (the town line to Hwy. 59)
- E. Deer Run Park Rd. (Hwy. 51 to end)
- Black Oak Dr. (Hwy 51 to end)
- Maple Beach Rd. (from Hillside to the town line)

between August 14<sup>th</sup> through August 24<sup>th</sup>, weather dependent. In case of rain or other unforeseen circumstances, this work will be done the next workweek.

Slag/Stone Aggregate operations will be performed on your road the week indicated above sometime between the hours of 7:00 am and 7:00 pm. Due to the number of streets scheduled, we do not know the exact time or date your street will be done.

No Parking will be allowed on any roads.

The Town has determined this is a very economical surface treatment that prolongs the life of the Town roads by reducing the pavement deterioration caused by weathering. Timely preventative maintenance like this prevents costly street reconstruction projects in the future. We realize the inconvenience caused by limiting access to your street, but this will be brief. Please understand that the inconvenience at this time is very small compared to what would later be required if this treatment was not applied. With your cooperation, it will be possible for the Town's Contractor to complete their work quickly and with minimum inconvenience.

Slag/Stone Aggregate is applied by using a thin layer of heated Asphalt Emulsion (oil) which is sprayed over the entire road surface and then covered by a thin layer of Slag/Stone Aggregate. The Aggregate is rolled or pressed onto the oil layer many times by a combination of a pneumatic (rubber) and steel wheel roller. Vehicular traffic is allowed immediately onto the Slag/Stone after the rolling has been completed. This process may last for about (30) minutes.

Once the road has been open, it is important for you to drive slowly and avoid any sharp turns or quick stops for about 7 to 10 days. Please be cautious when operating a motorcycle, bicycle, scooter and skateboard.

Most of the loose Aggregate will be **SWEPT & VACUUMED up**, 5-10 Days, after the rolling has been completed. Some loose Aggregate may remain on the street after the sweeping and vacuuming has been performed. **Please be aware you may track some residual loose Aggregate onto your driveway and into your house during this period.**

# TOWN OF FULTON

2738 W. Fulton Center Dr.  
Edgerton, Wisconsin 53534

Connie Zimmerman, WCMC, CMTW  
Clerk/Treasurer

Phone: 608-868-4103

Fax : 608-868-4104

Email: [fultonclerk@townoffulton.com](mailto:fultonclerk@townoffulton.com)

Web site: [www.townoffulton.com](http://www.townoffulton.com)

If you have any questions, please call the Town Chairman, Evan Sayre @ 608-774-4575

Thank you for your cooperation!  
Fulton Town Board